


Deployment #3

Welcome to Deployment 3!! Time to deploy to your customized VPC. You will need to follow the steps below and then add to the pipeline.

- First I installed Jenkins on an EC2
- Next, I created an EC2 in my Public Subnet of the Kura VPC that we created in class last week
- In the security groups for the Ubuntu EC2, I added ports number: 22 and 5000.
- I attempted to use the command sudo apt install to install the following packages: **default-jre**, **python3- pip**, **python3.10-venv and nginx**.
- I could not install python3-pip at first and I received the error "Package 'python3-pip' has no installation candidate". To fix this error I ran sudo apt update. Then, I was able to run sudo apt install python3-pip.
- I had to use sudo apt-get install -y python3-venv because sudo apt installdid not work. I also was then able to install nginx.

3. In order to configure and connect the Jenkins agents

 I entered my Jenkins server and selected the Build Executor status:



 Next, I selected "+ New Node" to configure and add the agent. I entered the node name "awsDeploy", then selected "Permanent Agent", and then I created the Node.




- ↑ Back to Dashboard
- Manage Jenkins
- + New Node
- Configure Clouds
- Node Monitoring



No builds in the queue.

Build Executor Status

Built-In Node



- Next I entered the configurations below:
- Name: awsDeploy
- Description: Deployment server
- O Number of executors: 1
- Remote root directory: /home/ubuntu/agent
- Labels: awsDeploy
- Usage: only build jobs with label expessions matching this node
- Launch method: launch agents via ssh
- I added the IP of my Public EC2 to the Host: 34.231.169.48
- These were the steps that I took to add the credentials.
 - Select "Add" => "Jenkins"=>Kind:"SSH username with private key"
 - Enter the ID, Description, username
 - To add the key, select "Enter Directly" => select "add" => paste the private key into the white box and save.

- O Availability: keep this agent online as much as possible
- Host key verification strategy: non verifying verification strategy


Advanced...




Jenkins Credentials Provider: Jenkins


Add Credentials

Domain Global credentials (unrestricted) Kind Username with password Username with password **AWS Credentials** GitHub App SSH Username with private key Secret file Secret text Certificate Username ? Treat username as secret ? Password ? ID ? Description ? Add Cancel





 I saved the configurations but Jenkins agent failed to launch because the credentials failed to authenticate. It turns out that I was missing a dash from the pem file.
 When I added the dash, the credentials authenticated and the Jenkins agent launched. Please see what my agent looked like below:



4. To create a Pipeline build in Jenkins:

 I first SSH'ed into the EC2 in my public VPC and used sudo to nano'ed into the "/etc/nginx/sites-enabled/default" file.

• In the file, I changed the port from 80 to 5000:

```
server {
listen 5000;
listen [::]:5000;
```

• I then scrolled down to "location" and replaced it with the text below:

 Next I edited the Jenkinsfile in my repo to the script below:

```
pipeline {
  agent any
   stages {
   stage ('Build') {
      steps {
        sh '''#!/bin/bash
        python3 -m venv test3
        source test3/bin/activate
        pip install pip --upgrade
        pip install -r requirements.txt
        export FLASK_APP=application
       flask run &
    }
   stage ('test') {
      steps {
        sh '''#!/bin/bash
        source test3/bin/activate
        py.test --verbose --junit-xml test-reports/results.xml
      }
     post{
        always {
         junit 'test-reports/results.xml'
        }
      }
```

```
}
stage ('Deploy') {
   agent{label 'awsDeploy'}
   steps {
    sh '''#!/bin/bash
      git clone https://github.com/kura-labs-org/kuralabs_deployment_2.git
    cd ./kuralabs_deployment_2
      python3 -m venv test3
      source test3/bin/activate
      pip install -r requirements.txt
      pip install gunicorn
      gunicorn -w 4 application:app -b 0.0.0.0 --daemon
      '''
}
}
```

 I configured a multi branch pipeline in Jenkins and connected Jenkins to my GitHub Repo but the build failed

Stage View Declarative: Build Deploy Checkout SCM Average stage times: 415ms 586ms 84ms 737ms 392ms 446ms 66ms 20:03 577ms 370ms 436ms 82ms Oct 08 873ms 383ms 441ms 19:59 516ms 5s 130ms

Once I installed the python virtual environment on Jenkins, the build was successful but the url shortner website would not come up. Once I modified the Jenkinsfile with the JENKINS_NODE_COOKIE=stayAlive, I was able to have successful build and I was able to deploy the url shortener website.

Also, I added the greeting modification from Deployment 2 to test file and I was able to have a successful build. Please see the screenshot below.

Stage View

